
















SITE RULES










All Exhibitors or Contractors working on site during the Construction phase (Build-up) and Dismantling phase (Breakdown) must adhere to the site rules below.

	You should not enter site if: <ul style="list-style-type: none"> You have any symptoms associated with COVID-19 You have tested positive for COVID-19
	If you develop COVID-19 symptoms whilst onsite you must leave site immediately
	No Unauthorised Access. Children under the age of 16 will not be permitted.
	No smoking in exhibition halls or marked outside areas.
	Drinking of alcohol onsite during the build up and breakdown phase is forbidden. The taking of illegal drugs is strictly forbidden at all times.
	Site speed limit of 10km/h must be adhered to at all times.
	PPE including high visibility clothing and safety footwear must be worn by all personnel onsite during the build up and breakdown. Open toed shoes will not be permitted. Hard hats must be worn in designated areas where overhead work taking place.
	
	A permit to work is required before any hot working commences.
	Machine and tool guards must always be used. Non-guarded machinery will not be permitted to be used and non-guarded tools will be confiscated.
	Emergency Gangways and fire exits must be kept clear at all times.
	Practice good respiratory hygiene and regularly wash your hands.
	Trailing cables must be minimised wherever possible. Where they are required they must be clearly identified and used for the minimum time possible.
	All temporary scaffold towers must be correctly built in line with manufacturer's instructions and persons erecting must be suitably trained and competent.
	All working at height must be planned to minimise risks involved so far as is reasonably practicable.



All Accidents, Incidents and near misses must be reported immediately to the Organisers office located in the East Entrance for AIX and Central Entrance Upper for WTCE.

Site Warnings:

	Caution – Slip & Trip Hazards
	Caution – Fork Lift trucks will be operating
	Caution – Crane operations & overhead working in designated areas
	Caution – Vehicle movement
	Caution – Working at height, danger of falling
	Caution – Live electrical installations
	Caution – Guard dogs on patrol
	CCTV in operation
	Unsafe working practices will not be tolerated. Work will ultimately be stopped and persons involved escorted offsite if practice or issue is not rectified.

Useful information:



The Medical Centre is located;

- Outside Hall B4 lower for AIX
- Outside Hall A2 for WTCE

If an ambulance is required, please do not call the emergency services directly. Inform a member of the exhibition team who will contact the relevant authorities, call 6666 from any internal phone or call +49 40 3569 6666 from a regular phone.

- Access passes for individuals to the site will be with wristbands issued onsite by the security team upon arrival
- There are many cafes/restaurant within close vicinity of the venue.
- There are permanent toilet facilities available within the hall.
- Drinking water will be available from the catering outlets around the venue. A map to identify the locations will be available from the organisers' office.



Site safety starts here

SAFETY SHOWS

RX In the business of building businesses